

ADDENDUM NO. 2

Phase II - Building Addition and Renovations for
St Clair Co – Administrative Building
Ashville, AL

H+HA Job No: 15002.00

July 11, 2016

A2-1 GENERAL:

- A2-1.1** The following changes and/or additions to the Contract Documents are hereby made part of same and are incorporated in full force as part of the contract.
- A2-1.2** Bidder shall acknowledge receipt of this Addendum on the Bid Form when submitting bid.

A2-2: REVISIONS/CLARIFICATIONS TO SPECIFICATIONS:

none

A2-3: REVISIONS/CLARIFICATIONS TO DRAWINGS:

- A2-3.1** Sheet A4.1, General Notes 1 & 2: Delete notes in their entirety
- A2-3.2** Sheet A4.1, Roof Keynotes:
02 – Revise note to read "Add Alt #1: Remove and replace existing prefinished metal coping with new break metal coping to match adjacent Phase I installation"
03 – Revise note to read "Add Alt #1: Remove existing membrane roofing at gutter, and any damaged rigid insulation/substrate. Replace any damaged insulation/substrate to match existing. Install new 60 mil PVC roofing membrane to match adjacent Phase I installation."
- A2-3.3** Sheet A4.1 – See attached original drawings from 2WR Architects, dated 11 – November, 1993, for roof parapet/gutter detailing: A6.0, A7.0, A12.0
- A2-3.4** Sheet A7.1, Detail 04/A7.1 – Hall Station Interior Elevation: change key mark from 04/A7.1 to 12/A7.1 to be associated with enlarged plan 03/A6.1.
- A2-3.5** Sheet A7.1, Details 08/A7.1, 09/A7.1 – Millwork Elevation at Probate Office: Details refer to modification of existing millwork island behind Probate Office counter, as indicated (but not keyed) on sheet A1.1, just below Recording Clerk 109. Intent is to duplicate existing "wine rack" style millwork on back side of existing, and install new countertop to cover both existing and new components.

END OF ADDENDUM NO. 2